

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>	1. CONTRACT ID CODE	PAGE OF PAGES 1   3
---	---------------------	------------------------

2. AMENDMENT/MODIFICATION NO. AM-0012	3. EFFECTIVE DATE 11 JUNE 2002	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable)
--	-----------------------------------	----------------------------------	--------------------------------

6. ISSUED BY US ARMY ENGINEER DISTRICT, HONOLULU CORPS OF ENGINEERS, BUILDING S-200 FORT SHAFTER, HAWAII 96858-5440 CONTRACT SPECIALIST: MARIA BUCKNER	CODE	7. ADMINISTERED BY (If other than Item 6)	CODE
--	------	---	------

8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)	(✓)	9A. AMENDMENT OF SOLICITATION NO. DACA83-02-B-0001
	X	9B. DATED (SEE ITEM 11) 12/11/01
		10A. MODIFICATION OF CONTRACTS/ORDER NO.
		10B. DATED (SEE ITEM 13)
CODE		FACILITY CODE

**11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers  is extended,  is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:  
 (a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

**13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

(✓)	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

**E. IMPORTANT:** Contractor  is not,  is required to sign this document and return \_\_\_\_\_ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

FY01 UMMCA PN 52070, ALIGN GATE, WHEELER ARMY AIRFIELD, OAHU, HAWAII  
 (SEE PAGES 2 AND 3 OF 3)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)	16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
15B. CONTRACTOR/OFFEROR  (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA  BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED

**1. CHANGES TO SPECIFICATIONS:** Attached hereto are revised pages to the specifications. The revision mark (Am-0012) is shown on each page.

**A. REVISED PARAGRAPHS :** Following are revised paragraphs to the specifications. Changes are indicated in **bold**. The following are revised paragraphs to the specifications.

Section 1900 MISCELLANEOUS PROVISIONS-Paragraphs: 1.8.1, 1.8.2, & 1.8.3.

**B. NEW PAGES.** The following new pages are added to the specifications.

None

**C. DELETED PAGES.** The following pages are deleted from the specifications.

None

**2. CHANGES TO DRAWINGS:**

**A. REVISED DRAWINGS (NOT ISSUED).** Following are revisions made to drawings listed. These revisions will not be issued with this amendment but will be furnished to the successful bidder at the time of award of the contract.

- (1) Drawing No. 851-90-05, Sheet No. T-2, Ring No. 2. At Zones A1, A2, A4, A5 and A6, add circled "d" to note revisions made to the following sheets:

<u>SHEET NO.</u>	<u>RING NO.</u>
C-2	4
C-5	9
C-6	10
C-17	21
C-18	22
C-26	30
C-27	31
CD-2	34

- (2) Drawing No. 851-90-05, Sheet No. C-18, Ring No. 22. At Zone B-5, revise turning movement radius from R = 60' to R = 70'.

**B. REVISED DRAWINGS (ISSUED).** The following revised drawings replace like-numbered drawings and are issued herewith:

<u>DRAWING NO.</u>	<u>SHEET NO.</u>	<u>RING NO.</u>	<u>REVISION LETTER</u>	<u>REVISION DATE</u>
851-90-05	C-2	4	d	5/21/02
851-90-05	C-5	9	d	5/21/02
851-90-05	C-6	10	d	5/21/02
851-90-05	C-17	21	d	5/21/02
851-90-05	C-26	30	d	5/21/02
851-90-05	C-27	31	d	5/21/02
851-90-05	CD-2	34	d	5/21/02

AM-0012  
IFB No. DACA83-02-B-0001  
Item 14 (Continued)

Standard Form 30  
Page 3 of 3 Page

**3. BID OPENING DATE, TIME AND LOCATION REMAINS UNCHANGED.**

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01900

MISCELLANEOUS PROVISIONS

PART 1 GENERAL

- 1.1 SUBMITTALS
  - 1.1.1 Progress Chart
  - 1.1.2 Products Containing Recovered Materials
  - 1.1.3 Recovered Material Report
  - 1.1.4 Excavation/Trenching Clearance
- 1.2 CONTRACTOR QUALITY CONTROL
- 1.3 AS-BUILT DRAWINGS
- 1.4 DUST CONTROL
- 1.5 PROTECTION
  - 1.5.1 Warning Signs and Barricades
  - 1.5.2 Protection of Grassed and Landscaped Areas
  - 1.5.3 Protection of Trees and Plants
  - 1.5.4 Protection of Building From the Weather
- 1.6 RESTORATION WORK
- 1.7 REMOVAL AND DISPOSAL
  - 1.7.1 Title to Materials
  - 1.7.2 Rubbish and Debris
- 1.8 INTERFERENCE WITH GOVERNMENT OPERATIONS
  - 1.8.1 Coordination**
  - 1.8.2 Existing Kunia Gate**
  - 1.8.3 Protection of Trees**
  - 1.8.4 Utilities and Facilities
  - 1.8.5 Staking and Flagging Existing Utilities
- 1.9 CONTRACTOR'S OPERATIONS OR STORAGE AREA
- 1.10 WORKING DIRECTIVES
  - 1.10.1 Working Hours
- 1.11 COORDINATION WITH UTILITY COMPANIES
- 1.12 USE OF PRODUCTS CONTAINING RECOVERED MATERIALS

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

-- End of Section Table of Contents --

SECTION 01900

MISCELLANEOUS PROVISIONS

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Progress Chart.

SD-02 Shop Drawings

As-Built Drawings.

SD-07 Certificates

Products Containing Recovered Materials.

SD-08 Manufacturer's Instructions

Recovered Material Report

Dust Control.

Method(s) of dust control.

Excavation/Trenching Clearance

Prior to start of any excavation or trenching work, the Contractor shall obtain clearance, in writing, from the appropriate communications agency and base or area engineer. Copies of all correspondence shall be provided the Contracting Officer. Normal coordination time for obtaining the necessary permits is approximately fifteen (15) calendar days. The Contractor shall advise the Contracting Officer promptly when it appears that the normal coordination time will be exceeded.

Condition of Contractor's Operations or Storage Area

The Contractor shall submit to the Contracting Officer photographs and/or videos depicting the condition of the Contractor's Operation or Storage Area.

1.1.1 Progress Chart

The Contractor shall prepare and submit for approval by the Contracting Officer a progress chart in accordance with the CONTRACT CLAUSE entitled

"SCHEDULE FOR CONSTRUCTION CONTRACTS" twenty-one (21) calendar days prior to initiation of any work. Any material change to the progress chart must be approved in writing in advance by the Contracting Officer. Any proposed changes to the approved schedule shall be requested by the Contractor in writing a minimum of fourteen (14) calendar days prior to the proposed start of work.

#### 1.1.2 Products Containing Recovered Materials

The Contractor shall submit manufacturer's certification attesting that product meets or exceeds EPA's recovered material guidelines.

#### 1.1.3 Recovered Material Report

The Contractor shall provide a report listing all products meeting EPA guidelines for products containing recovered materials and quantity used for this project.

#### 1.1.4 Excavation/Trenching Clearance

Prior to start of any excavation or trenching work, the Contractor shall obtain clearance, in writing, from the appropriate communications agency and base or area engineer. Copies of all correspondence shall be provided the Contracting Officer. Normal coordination time for obtaining the necessary permits is approximately fifteen (15) calendar days. The Contractor shall advise the Contracting Officer promptly when it appears that the normal coordination time will be exceeded.

### 1.2 CONTRACTOR QUALITY CONTROL

To assure compliance with contract requirements, the Contractor shall establish and maintain quality control for materials and work covered by all sections of the TECHNICAL REQUIREMENTS in accordance with Section 01451 CONTRACTOR QUALITY CONTROL. Records shall be maintained for all operations including sampling and testing.

### 1.3 AS-BUILT DRAWINGS

As-built drawings shall be in accordance with Section 01780 CLOSEOUT SUBMITTALS.

### 1.4 DUST CONTROL

The amount of dust resulting from the Contractor's work shall be controlled to prevent the spread of dust to occupied portions of the construction site and to avoid creation of a nuisance in the surrounding area. Use of water will not be permitted when it will result in, or create, hazardous or objectionable conditions such as flooding and pollution. Measures shall also be taken for dust control along haul routes and equipment parking areas.

### 1.5 PROTECTION

The Contractor shall take all necessary precautions to insure that no damages to private or public property will result from his operations. Any such damages shall be repaired or property replaced by the Contractor in accordance with the CONTRACT CLAUSES entitled "PERMITS AND RESPONSIBILITIES" and "PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS", without delay, and at no cost to

the Government.

#### 1.5.1 Warning Signs and Barricades

The Contractor shall be responsible for posting warning signs or erecting temporary barricades to provide for safe conduct of work and protection of property.

#### 1.5.2 Protection of Grassed and Landscaped Areas

The Contractor's vehicles shall be restricted to paved roadways and driveways. Vehicles shall not be driven or parked on grassed and/or landscaped areas except when absolutely necessary for the performance of the work and approved in advance by the Contracting Officer. Grassed or landscaped areas damaged by the Contractor shall be restored to their original condition without delay and at no cost to the Government.

#### 1.5.3 Protection of Trees and Plants

Where necessary, tree branches and plants interfering with the work may be temporarily tied back by the Contractor to permit accomplishment of the work in a convenient manner, so long as they will not be permanently damaged thereby. If this is not feasible, they may be pruned, subject to written approval by the Contracting Officer.

#### 1.5.4 Protection of Building From the Weather

The interior of the building and all materials and equipment shall be protected from the weather at all times.

#### 1.6 RESTORATION WORK

Existing conditions or areas damaged or disturbed by the Contractor's operations shall be restored to their original condition, or near original condition as possible, to the satisfaction of the Contracting Officer.

#### 1.7 REMOVAL AND DISPOSAL

The Contractor shall salvage or recycle waste to the maximum extent practical as it relates to the capabilities of local industries. A record of the quantity of salvaged or recycled materials shall be maintained by the Contractor during the length of the project and submitted to the Contracting Officer at acceptance of the project. Quantities shall be recorded in the unit of measure of the industry. Reuse of materials on the site shall be considered a form of recycling. An example of such reuse would be the use of acceptable excavated materials as fill.

##### 1.7.1 Title to Materials

Title to all materials and equipment to be removed, except as indicated or specified otherwise, is vested in the Contractor upon receipt of notice to proceed. The Government will not be responsible for the condition, loss or damage to such property after the Contractor's receipt of notice to proceed. Items indicated to be removed shall be removed and disposed of by the Contractor outside the limits of Government-controlled property at the Contractor's responsibility and expense before the completion and final acceptance of the work, and such materials shall not be sold on the site.

##### 1.7.2 Rubbish and Debris

Rubbish and debris shall be removed from Government-controlled property daily unless otherwise directed, so as not to allow accumulation inside or outside the building. Materials that cannot be removed daily shall be stored in areas designated by the Contracting Officer.

#### 1.8 INTERFERENCE WITH GOVERNMENT OPERATIONS

The Contractor shall establish work procedures and methods to prevent interference with existing operations within or adjacent to the construction area. Free passage into adjoining or adjacent buildings not in the contract will not be permitted except as approved by the Contracting Officer. Procedures and methods shall also provide for safe conduct of work and protection of property which is to remain undisturbed.

##### 1.8.1 Coordination

Perform all work with extreme care to avoid damage to existing construction and installations, ensure necessary provisions to keep interferences to a minimum. Coordinate all work with the Contracting Officer minimize interruption and to cause the least possible inconvenience to Government activities. Scheduling and programming of work will be established during the pre-construction conference.

##### 1.8.2 Existing Kunia Gate

Ensure continuous operation of the existing Kunia Gate. Closure of the existing Kunia Gate will be permitted only after the new gate is fully operational. Security at the gates shall be maintained at all times during construction of new gate.

##### 1.8.3 Protection of Trees

Several trees within Wheeler Army Airfield along Wright Avenue are identified on the Honolulu Register of Exceptional Trees by the City and County of Honolulu, and shall be protected from damage. The Army Department of Public Works will obtain permits from the City and County of Honolulu for work around the vicinity of the trees. Conduct work in accordance with the City ordinances for protection of trees.

##### 1.8.4 Utilities and Facilities

All utilities and facilities within the area shall remain operable and shall not be affected by the Contractor's work, unless otherwise approved in writing in advance by the Contracting Officer.

##### 1.8.5 Staking and Flagging Existing Utilities

The Contractor, prior to start of any excavation or trenching work, shall verify the location of all utility lines shown on the drawings which are within the areas of work, and shall mark, stake, or flag each utility line along trench alignments and under areas of excavation under this project, as approved. Existing utility lines shall be located by walking trench alignments with approved equipment for locating underground pipes and cables. Utility lines so located shall be noted on the drawings.

#### 1.9 CONTRACTOR'S OPERATIONS OR STORAGE AREA

At the request of the Contractor, an open operations or storage area will

be made available within the installation, the exact location shall be as indicated. The Contractor shall be responsible for the security necessary for protection of his equipment and materials, and shall maintain the area free of debris. No rusty or unsightly materials shall be used for providing the secure measure and such measure shall be erected in a workmanlike manner. Before any construction commences on establishing the operation/storage area, Contractor shall take photographs and/or videos of the site in order to establish the original conditions of the site. A duplicate set shall be made and submitted to the Government for its files. Upon completion and prior to the final acceptance of the contract work, the Contractor shall restore the area to its original condition.

#### 1.10 WORKING DIRECTIVES

##### 1.10.1 Working Hours

All work shall be performed between the hours of 0730 to 1600 HST, Monday through Friday. No work shall be accomplished on Saturdays, Sundays, and all federal holidays without written permission from the Contracting Officer. Such written permission shall be available at the job site at all times during construction.

#### 1.11 COORDINATION WITH UTILITY COMPANIES

Contractor shall coordinate with Hawaiian Electric Company (HECO), Verizon Hawaii (VZ), and Oceanic Cable, and pay required fees for the installation of the new joint use poles and relocation of cables. The respective proposal letters by HECO (dated September 6 & 28, 2001), Oceanic Cable (dated September 7, 2001), and VZ (dated September 7, 2001), are attached at the end of this section.

#### 1.12 USE OF PRODUCTS CONTAINING RECOVERED MATERIALS

Recovered materials are materials manufactured from waste material and byproducts that have been recycled or diverted from solid waste. The Contractor shall give preference to products containing recovered material when price, performance, and availability meet project requirements. A listing of products, including the recommended recovered material content, is provided by the Environmental Protection Agency at <http://www.epa.gov/cpg/products.htm>. Only those products having recovered material content equal to or greater than EPA guidelines shall be used to meet this requirement.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

-- End of Section --